



No. NCA/Bldg/Maint./2018-19/

Date : 21.02.2019

NOTICE INVITING TENDER

Director (Civil), Narmada Control Authority, Narmada Sadan, Sch. No. 74, Block-B, Indore on behalf of the Chairman, Narmada Control Authority invites item rate tenders in sealed cover from the eligible contractors registered with CPWD, state PWD, MES, BSNL, Railways, Housing Board & other Govt. Department in appropriate classes for the under mentioned work upto 14.00 hrs. **on 06/03/2019**

| S. No. | Name of work | Estimated cost (Rs.) | Earnest money (Rs.) | Time of completion of works | Last Date and time for receive of application for tender | Last date & time for sale of tender | Last date & time for receiving tender | Date and time for opening of tender | Cost of Tender document (Rs.) |
|--------|--|----------------------|---------------------|-----------------------------|--|-------------------------------------|---------------------------------------|-------------------------------------|-------------------------------|
| 1. | Raising of Boundary Wall at the NVDA side of Narmada Sadan, Sch. No. 74-C, Vijay Nagar Indore | 1,31,300/- | 2650/- | 15 days | 05.3.19 upto 1400 Hrs | 05.3.19 upto 1600 Hrs | 06.3.19 upto 1400 Hrs | 06.3.19 upto 1600 Hrs | 500/- |

- The tender document for above mentioned works shall be issued to interested Contractors/Agency from the Account Section, NCA, 'Narmada Sadan, Block-B, Scheme, No. 74, Vijaynagar, Indore on all days except (Saturday, Sunday and Govt. Holiday) during the office hours on his request subject to production of self attested copy of PAN card and payment of cost of Tender Document (Non refundable) as indicated above. Through cash/ Demand Draft drawn in favour of **Narmada Control Authority, payable at Indore.**
- The earnest money should be submitted as prescribed in CPWA-6 form attached with the tender document.
- The contractor should fulfill the eligibility criteria of having successfully completed works of similar nature and amount as mentioned in Para 1.1.2 of CPWA-6 form and having valid PAN card. Attested copies of relevant documents are required to be submitted along with Bid document in original.
- Notice inviting tender (NIT) and tender document are also available on NCA website **www.nca.gov.in**. In case, the agency/firm downloads the tender documents from the website, he will have to deposit the cost of tender documents by demand draft along with the tender at the time of submission of tender failing which tender shall be rejected without assigning any reason there of.

Sd/-

Director (Civil)

G-Schedule

**Name of work: Raising of Boundary Wall at the side of Narmada Sadan,
Sh. No.74-C, Vijay Nagar Indore**

| Sl. No | Item | Unit | Qty. | Rate | Amount (Rs.) |
|--------------|--|------|--------|------|--------------|
| 1 | Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge. | Cum | 0.09 | | |
| 2 | Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. | Cum | 0.09 | | |
| 3 | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size). | Cum | 4.19 | | - |
| 4 | Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts Centering and shuttering above all the Columns for supporting the PCC | Sqm. | 53.36 | | |
| 5 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more | Kg. | 284.62 | | |
| 6 | Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) : | Cum | 3.83 | | |
| 7 | Plastering 20 mm cement plaster of mix 1:4 (1 cement : 4 fine sand) | Sqm. | 139.44 | | |
| 8 | Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm) | Sqm. | 151.06 | | |
| 9 | Providing and fixing glass pieces at the top of the coping of Boundary wall to provide proper Hurdle at the top | Job | 1.00 | | |
| Total | | | | | |