



निविदा आमंत्रण सूचना

निदेशक (सिविल), नर्मदा नियंत्रण प्राधिकरण, नर्मदा भवन, योजना क्रमांक 74, ब्लॉक-बी, विजय नगर, इन्दौर द्वारा एतद् अध्यक्ष, नर्मदा नियंत्रण प्राधिकरण की ओर से निम्नलिखित कार्य के लिये केन्द्रीय लोक निर्माण विभाग, एम.ई.एस. मध्यप्रदेश लोक निर्माण विभाग, जल संसाधन विभाग, भारत सरकार एवं राज्य सरकार के अन्य सरकारी उपक्रमों में उचित श्रेणी में पंजीकृत अथवा अनुमोदित योग्य ठेकेदारों से दिनांक 06/03/2019 के 14.00 बजे तक मद दर मोहरबंद निविदाएं नीचे दिए विवरणानुसार आमंत्रित की जाती है ।

क्र.	कार्य का नाम	अनुमानित लागत राशि रु.	धरोहर राशि रु.	कार्य पूर्ण करने की अवधि	निविदा प्राप्ति हेतु आवेदन की अंतिम तिथि एवं समय	निविदा विक्रय की अंतिम तिथि एवं समय	निविदा जमा करने की अंतिम तिथि एवं समय	निविदा खोलने की तिथि एवं समय	निविदा प्रपत्र मूल्य रु. (नगद वापसी योग्य नहीं)
1.	योजना क्र. 74 स्थित नर्मदा सदन, विजय नगर, इन्दौर के पास एवं नर्मदा घाटी विकास प्राधिकरण के साईड वाली दीवार को ऊँचा उठाने के कार्य हेतु।	1,31,300/-	2650/-	15 दिन	05.03.19 1400 बजे तक	05.03.19 1600 बजे तक	06.3.19 1400 बजे तक	06.3.19 1600 बजे	500/-

- उपरोक्त कार्यों के लिये इच्छुक ठेकेदार निविदा प्रपत्र, निर्धारित मूल्य का नगद भुगतान अथवा नर्मदा नियंत्रण प्राधिकरण के नाम से डीमाण्ड ड्रफ्ट जो कि इन्दौर में देय हो के द्वारा (वापसी योग्य नहीं) लेखा शाखा के कार्यालय, न.नि.प्रा., नर्मदा सदन, योजना क्रमांक 74-सी, ब्लॉक-बी, विजयनगर, इन्दौर से प्रत्येक कार्य दिवस (शनिवार, रविवार एवं शासकीय अवकाश को छोड़कर) में प्रातः 11 बजे से 16.00 बजे तक करके प्राप्त कर सकते हैं ।
- धरोहर राशि निविदा प्रपत्र के साथ संलग्न सी.पी.डब्ल्यू.ए. फार्म-6 में दिए गए उचित प्रारूप में निविदा के साथ जमा करनी होगी ।
- एजेन्सी के पास इसी तरह के व इतनी राशी के कार्य सफलतापूर्वक पूर्ण करने के प्रमाण सी.पी.डब्ल्यू.ए. फार्म-6 के पेरा 1.1.2 में दिये गये अनुसार तथा वैद्य पान कार्ड होना चाहिए सभी संबंधित दस्तावेजों की सत्यापित प्रतिलिपि मूल निविदा के साथ प्रस्तुत जमा की जानी चाहिए ।
- निविदा आमंत्रण सूचना एवं निविदा प्रपत्र नर्मदा नियंत्रण प्राधिकरण के वेबसाईट www.nca.gov.in पर भी देखा जा सकता है । यदि कोई एजेन्सी निविदा प्रपत्र वेबसाईट से डाउनलोड करके निविदा प्रस्तुत करती है तो उसे निविदा प्रपत्र मूल्य का ड्राफ्ट निविदा के साथ जमा करना होगा अन्यथा बिना कोई कारण बताए निविदा निरस्त मानी जाएगी ।

ह-

निदेशक (सिविल)

G-Schedule

**Name of work: Raising of Boundary Wall at the side of Narmada Sadan,
Sh. No.74-C, Vijay Nagar Indore**

Sl. No	Item	Unit	Qty.	Rate	Amount (Rs.)
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	Cum	0.09		
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cum	0.09		
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	Cum	4.19		-
4	Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts Centering and shuttering above all the Columns for supporting the PCC	Sqm.	53.36		
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	Kg.	284.62		
6	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) :	Cum	3.83		
7	Plastering 20 mm cement plaster of mix 1:4 (1 cement : 4 fine sand)	Sqm.	139.44		
8	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm.	151.06		
9	Providing and fixing glass pieces at the top of the coping of Boundary wall to provide proper Hurdle at the top	Job	1.00		
Total					